



PREFLIGHT

- | | |
|------------------------|----------------|
| 1 Documents | ARROW |
| 2 Tach/Hobbs | NOTE |
| 3 Fuel | CHECK VISUALLY |
| 4 Oil | MIN 5 QUARTS |
| 5 Tires (nose/mains) | 45/38 PSI |
| 6 Emergency Equip | CHECK |
| 7 Alternate Static | NORMAL |
| 8 Circuit Breakers | IN |
| 9 Electrical Equip | OFF |
| 10 Avionics Bus 1 & 2 | OFF |
| 11 ALT & BAT Masters | ON |
| 12 PFD | VERIFY ON |
| 13 Fuel Quantity Ind | CHECK |
| 14 Low Fuel Annunc | OFF |
| 15 Oil Pres & Vac Ann | VERIFY ON |
| 16 Avionics Bus 1 | ON |
| 17 Fwd Avionics Fan | AUDIBLE |
| 18 Avionics Bus 1 | OFF |
| 19 Avionics Bus 2 | ON |
| 20 Aft Avionics Fan | AUDIBLE |
| 21 Avionics Bus 2 | OFF |
| 22 Flaps | DOWN |
| 23 Lights & Stall Horn | CHECK |
| 24 Low Volts Annunc | VERIFY ON |
| 25 ALT & BAT Masters | OFF |
| 26 Exterior Inspection | COMPLETE |

BEFORE START

- | | |
|----------------------|-------------------|
| 1 Passenger Briefing | COMPLETE |
| 2 Seats & Belts | ADJUST & SECURE |
| 3 Brakes | TEST & SET |
| 4 Circuit Breakers | CHECK |
| 5 Electrical Equip | OFF |
| 6 Avionics Bus 1 & 2 | OFF |
| 7 Fuel Selector | BOTH |
| 8 Fuel Shutoff | ON (PUSH FULL IN) |

START

- | | |
|----------------------|-----------------|
| 1 Throttle | OPEN 1/4 INCH |
| 2 Mixture | IDLE CUTOFF |
| 3 Stby Batt TEST | LIGHT ON 20 SEC |
| 4 Stby Batt ARM | PFD ON |
| 5 Engine Indications | NO RED X's |
| 6 Bus E Volts | 24 VOLTS MIN |
| 7 Bus M Volts | 1.5 VOLTS MAX |
| 8 Battery S Amps | DISCHARGING |
| 9 Stby Batt Annuc | VERIFY ON |
| 10 ALT & BAT Masters | ON |
| 11 Beacon | ON |
- If engine is warm, omit steps 12-14 below*
- | | |
|-----------------------|-------------------|
| 12 Fuel Pump | ON |
| 13 Mixture | RICH 3-5 SEC |
| 14 Fuel Pump | OFF |
| 15 Magnetos | CLEAR PROP, START |
| 16 Mixture | ADJ SMOOTH OPS |
| 17 Oil Pressure | GREEN W/IN 30 SEC |
| 18 Amps (M & S) | CHARGING |
| 19 Low Volts Annunc | NOT SHOWN |
| 20 Lights | AS REQUIRED |
| 21 Flaps | UP |
| 22 Avionics Bus 1 & 2 | ON |

RUNUP

- | | |
|------------------------|--------------------|
| 1 Parking Brake | SET |
| 2 Seats, Backs & Belts | UP, SECURE, LOCKED |
| 3 Cabin Doors | CLOSED & LATCHED |
| 4 Flight Controls | FREE & CORRECT |
| 5 Autopilot | CHECK & OFF |
| 6 PFD | NO RED X's |
| 7 Alt (PFD, Stby, A/P) | SET QNH |
| 8 Stby Flight Instrum | CHECK |
| 9 Fuel Quantity | CHECK |
| 10 Mixture | RICH or SET for DA |

Alt Sel: PFD A/P Alt

YEARS: 2005+
S/N: 17259810+ G1000

Published by Javaz Ventures, Inc. dba Qref Quick Reference Media™ ("Qref").
Copyright © 2009 by Gene Hudson of Slant Golf, Inc. and Jason Clemens of Qref.

Notice of Liability: This abbreviated checklist does not supersede any official regulations, procedures or documents. No warranty is expressed or implied. The author, publisher, and manufacturers will not be liable for any damages caused or thought to be caused, directly or indirectly, by the information in this material.

11 Fuel Selector	BOTH
12 Electric Trim (opt)	CHECK
13 Throttle	1800 RPM
14 Magnetos	150 / 50
15 Engine Indicators	CHECK
16 Amps & Volts	CHECK
17 Annunciators	NONE SHOWN

MFD: GPS1&2 Updt Fuel

TAKEOFF

1 Mixture	RICH or SET for DA
2 Elevator Trim	TAKEOFF
3 Flaps	10°
4 Annunciators	NONE SHOWN
5 Lights	ON AS REQUIRED
6 T/O, Dep & Emerg	BRIEFED
7 Time	NOTE
8 Parking Brake	RELEASE
9 Throttle	FULL
10 Rotate	55 KIAS
11 Climb Speed	70 - 80 KIAS
12 Flaps	UP AT SAFE ALT

CLIMB

1 Airspeed (Norm)	70 - 85 KIAS
Vx (SL/10k MSL)	62 / 72 KIAS
Vy (SL/10k MSL)	74 / 72 KIAS
2 Throttle	FULL
3 Mixture	LEAN above 3k MSL

CRUISE

1 Power	55% - 75%
2 Mixture	LEAN

DESCENT

1 Mixture	ADJ SMOOTH OPS
2 Fuel Selector	BOTH
3 Alt (PFD, Stby, A/P)	SET

BEFORE LANDING

1 Seats, Backs & Belts	UP, SECURE, LOCKED
2 Fuel Selector	BOTH
3 Mixture	RICH
4 Ldg & Taxi Lights	ON
5 Autopilot	OFF
6 12V Pwr (opt.)	OFF

BALKED LANDING

1 Throttle	FULL
2 Rate of Climb	POSITIVE
3 Flaps	RETRACT TO 20°
4 Airspeed	60 KIAS
5 Flaps	10°

After obstacles are cleared...

6 Airspeed	65 KIAS
7 Flaps	UP AT SAFE ALT

AFTER LANDING

1 Flaps	UP
2 Pitot Heat	OFF
3 Lights	AS REQUIRED

SHUTDOWN

1 Parking Brake	SET
2 Flight Plan	CLOSED
3 Tach & Hobbs	RECORD
4 Electrical Equip	OFF
5 Av Bus 1 & Bus 2	OFF
6 Mixture	IDLE CUTOFF
7 Magneto Switch	OFF
8 ALT & BAT Masters	OFF
9 Stby Batt	OFF
10 Fuel Selector	LEFT or RIGHT
11 Control Lock	INSTALL
12 Tie-downs, Chocks	INSTALL
13 Parking Brake	RELEASE

TERMINAL CHART (MM)

2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23





AUTOPILOT OR ELECTRIC TRIM MALFUNCTION

- | | | |
|---|-------------------|--------------|
| 1 | Airplane Control | MAINTAIN |
| 2 | AVP Disc/Trim INT | PRESS & HOLD |
- IF** *If autopilot does not disengage...*
- | | | |
|---|-------------------|----------------|
| 3 | Autopilot Breaker | PULL |
| 4 | Throttle | AS REQUIRED |
| 5 | Control Yoke | MANUALLY HOLD |
| 6 | Divert | NRST ALTERNATE |

IF *If autopilot still does not disengage...*

- | | | |
|---|----------------|-----|
| 7 | Avionics Bus 2 | OFF |
|---|----------------|-----|
- IF** *If autopilot still does not disengage, and flight is in visual conditions...*

- | | | |
|----|-------------------|----------------|
| 8 | ALT & BAT Masters | OFF |
| 9 | Stby Batt | OFF |
| 10 | Divert | NRST ALTERNATE |

CABIN FIRE IN FLIGHT

- | | | |
|---|-------------------|----------|
| 1 | Emerg. Descent | INITIATE |
| 2 | Stby Batt | OFF |
| 3 | ALT & BAT Masters | OFF |
| 4 | Vents/Air/Heat | CLOSED |
| 5 | Fire Extinguisher | ACTIVATE |

IF *If fire is not extinguished...*

- | | | |
|---|----------------|---------|
| 6 | Emerg. Landing | EXECUTE |
|---|----------------|---------|

IF *If fire is completely extinguished...*

- | | | |
|---|----------------|---------|
| 6 | Emerg. Descent | ABORT |
| 7 | Divert | NEAREST |
| 8 | Cabin | VENT |

CO LEVEL HIGH

- | | | |
|---|-----------------|------|
| 1 | Cabin Heat | OFF |
| 2 | Cabin Air | ON |
| 3 | Vents & Windows | OPEN |

IF *If CO Level Annunciator remains on...*

- | | | |
|---|------|----------------|
| 4 | Land | NRST ALTERNATE |
|---|------|----------------|

EMERGENCY LANDING WITHOUT ENGINE POWER

- | | | |
|---|---------------------------|------------------|
| 1 | Turn Towards Safe Terrain | |
| 2 | Seats, Backs, Belts | SECURE, UP, LOCK |
| 3 | Airspeed (flaps u/d) | 70 KIAS/65 KIAS |
| 4 | Mixture | IDLE CUTOFF |
| 5 | Fuel Shutoff | OFF (PULL OUT) |
| 6 | Magnetos | OFF |
| 7 | Flaps | AS REQUIRED |
| 8 | Stby Batt | OFF |

When landing is assured...

- | | | |
|----|-------------------|---------|
| 9 | ALT & BAT Masters | OFF |
| 10 | Doors | UNLATCH |

ENGINE FAILURE AFTER TAKEOFF

- | | | |
|---|----------------------|-----------------|
| 1 | Airspeed (flaps u/d) | 70 KIAS/65 KIAS |
| 2 | Mixture | OFF |
| 3 | Fuel Shutoff Valve | OFF (PULL OUT) |
| 4 | Magnetos | OFF |
| 5 | Flaps | AS REQUIRED |
| 6 | Stby Batt | OFF |
| 7 | ALT & BAT Masters | OFF |
| 8 | Cabin Door | UNLATCH |
| 9 | Land | STRAIGHT AHEAD |

ENGINE FAILURE IN FLIGHT

- | | | |
|---|---------------|--------------|
| 1 | Airspeed | 68 KIAS |
| 2 | Fuel Shutoff | ON (PUSH IN) |
| 3 | Fuel Selector | BOTH |
| 4 | Fuel Pump | ON |
| 5 | Mixture | RICH |
| 6 | Magnetos | BOTH |

IF *If propeller is stopped...*

- | | | |
|----|-----------|----------------|
| 7 | Magnetos | START |
| 8 | Throttle | ADVANCE |
| 9 | Mixture | ADJ SMOOTH OPS |
| 10 | Fuel Pump | OFF |

YEARS: 2005+
S/N: 17259810+ G1000

ENGINE FIRE IN FLIGHT

- | | | |
|---|-------------------|-------------------------|
| 1 | Mixture | IDLE CUTOFF |
| 2 | Fuel Shutoff | OFF (PULL OUT) |
| 3 | Fuel Pump | OFF |
| 4 | ALT & BAT Masters | OFF |
| 5 | Cabin Heat & Air | OFF |
| 6 | Overhead Vents | OPEN |
| 7 | Airspeed | 100 KIAS OR MORE |
| 8 | Emerg Landing | EXECUTE |

FUEL FLOW FLUCTUATIONS

- | | | |
|---|---------------|----------------|
| 1 | Fuel Pump | ON |
| 2 | Mixture | ADJ SMOOTH OPS |
| 3 | Fuel Selector | OPPOSITE TANK |

After fuel flow has stabilized...

- | | | |
|---|-----------|-----|
| 4 | Fuel Pump | OFF |
|---|-----------|-----|

HIGH VOLTS ANNUNCIATOR ON

- | | | |
|---|-----------------|----------------|
| 1 | ALT Master | OFF |
| 2 | Electrical Load | REDUCE |
| 3 | Land | NRST ALTERNATE |

LOW VOLTS ANUNCIATOR ON

- | | | |
|---|---------------------|---------------|
| 1 | ALT Master | OFF |
| 2 | Alternator Field CB | CHECK IN |
| 3 | ALT & BAT Masters | ON |
| 4 | Low Volts Annunc | CHECK OFF |
| 5 | M BUS VOLTS | 27.5V MINIMUM |
| 6 | M BAT AMPS | CHARGING (+) |

IF *LOW VOLTS remains on...*

- | | | |
|---|-----------------|----------------|
| 7 | ALT Master | OFF |
| 8 | Electrical Load | REDUCE |
| 9 | Land | NRST ALTERNATE |

OIL PRESSURE LOW (<20 PSI)

- | | | |
|---|----------|----------------|
| 1 | Throttle | MIN REQUIRED |
| 2 | Land | NRST ALTERNATE |

OIL PRESS OR TEMP HIGH

- | | | |
|---|------------|-------------------------|
| 1 | Climb Rate | REDUCE |
| 2 | Airspeed | 100 KIAS OR MORE |
| 3 | Mixture | ENRICHEN |
| 4 | Throttle | REDUCE |

IF *Oil Press remains on after one minute...*

- | | | |
|---|-------|----------------|
| 5 | Power | MIN REQUIRED |
| 6 | Land | NRST ALTERNATE |

PRECAUTIONARY LND W/POWER

- | | | |
|---|-------------------|------------------|
| 1 | Flaps | 20° |
| 2 | Selected Field | OVERFLY, INSPECT |
| 3 | On final, Flaps | FULL |
| 4 | Airspeed | 65 KIAS |
| 5 | Stby Batt | OFF |
| 6 | ALT & BAT Masters | OFF |
| 7 | Doors | PROP OPEN |
| 8 | Mixture | IDLE CUTOFF |
| 9 | Magnetos | OFF |

SMOKE & FUME ELIMINATION

IF *Source unknown, do Cabin Fire Checklist*

- | | | |
|---|------------------|----------------|
| 1 | Divert | NRST ALTERNATE |
| 2 | Heat & Fan | OFF |
| 3 | Temp Selector | COLD |
| 4 | Airflow Selector | FULL ON |
| 5 | Cabin Windows | OPEN |

IF *Airflow not enough to clear smoke/fumes...*

- | | | |
|---|-------------|----------------|
| 6 | Cabin Doors | PARTIALLY OPEN |
| 7 | Land | IMMEDIATELY |

WING FIRE IN FLIGHT

- | | | |
|---|---------------------|-----------|
| 1 | Emerg Descent | INITIATE |
| 2 | Pitot Heat & Lights | OFF |
| 3 | Wings | SIDE SLIP |

! *Side-slip to keep flames away cabin*

IF *Fire not extinguished, land immediately*

